

# ＊ ＊ 本工事費 ＊ ＊ 内訳表

頁0-0001

費目・工種・施工名称・管理費区分	数	量	単 位	金 額	備 考
＊ ＊ 本工事費 ＊ ＊					
道路修繕					
舗装工			式	7,953,009	
舗装打換え工			式	7,250,309	
舗装版切断			式	7,250,309	
			一式		舗装版切断
					200 m
舗装版破碎			一式		
					舗装版破碎
					1,310 m2
殻運搬			一式		

# ＊ ＊ 本工事費 ＊ ＊ 内訳表

頁0-0002

費目・工種・施工名称・管理費区分		数	量	単	位	金	額	備	考
								殻運搬	
殻処分								79	m3
					一式				
								廃材処理費 アスファルト舗装廃材	
掘削								185	t
					一式				
								掘削	
土砂等運搬								90	m3
					一式				
								土砂等運搬	
整地								90	m3
					一式				
								整地	
								90	m3

# ＊ ＊ 本工事費 ＊ ＊ 内訳表

頁0-0003

費目・工種・施工名称・管理費区分	数	量	単 位	金 額	備 考
上層路盤					
			一式		
					不陸整正
					1,310 m2
基層					
			一式		
					基層(車道・路肩部)
					1,310 m2
表層					
			一式		
					表層(車道・路肩部)
					1,310 m2
目地					
			一式		
区画線工					
			式	237,060	
区画線工					
			式	237,060	

# ＊ ＊ 本工事費 ＊ ＊ 内訳表

頁0-0004

費目・工種・施工名称・管理費区分		数	量	単	位	金	額	備	考
溶融式区画線									
					一式				
								区画線設置	
								380	m
								区画線設置	
								95	m
								区画線設置	
								42	m
								区画線設置	
								35	m
仮設工									
					式		465,640		
交通管理工									
					式		465,640		
交通誘導警備員									
					一式				
								交通誘導警備員B	
								28.0	人日

# ＊ ＊ 本工事費 ＊ ＊ 内訳表

頁0-0005

費目・工種・施工名称・管理費区分		数	量	単	位	金	額	備	考
直接工事費									
							7,953,009		
共通仮設費（率分）									
							1,824,000		
共通仮設費計									
							1,824,000		
純工事費									
							9,777,009		
現場管理費（率分）									
							4,646,000		
現場管理費計									
							4,646,000		
工事原価									
							14,423,009		
工事原価計									
							14,423,009		
一般管理費等									
							3,061,991		

# ＊ ＊ 本工事費 ＊ ＊ 内訳表

頁0-0006

費目・工種・施工名称・管理費区分		数	量	単	位	金	額	備	考
契約保証費									
							5,000		
一般管理費等計									
							3,066,991		
工事価格									
							17,490,000		