

＊ ＊ 本工事費 ＊ ＊ 内訳表

頁0-0001

費目・工種・施工名称・管理費区分	数	量	単	位	金	額	備	考
＊ ＊ 本工事費 ＊ ＊								
道路改良								
				式	8,176,084			
道路土工								
				式	1,475,738			
							掘削	
							260	m3
							路床盛土	
							10	m3
							土砂等運搬	
							270	m3
排水構造物工								
				式	6,316,118			
							床掘り	
							130	m3
							床掘り	
							9	m3

07-実施-一般-0003-当初

＊ ＊ 本工事費 ＊ ＊ 内訳表

頁0-0002

費目・工種・施工名称・管理費区分	数	量	単	位	金	額	備	考
							埋戻し	
							90	m3
							埋戻し	
							7	m3
							基面整正	
							178	m2
							自由勾配側溝	
							273	m
							自由勾配側溝	
							10	m
							自由勾配側溝	
							8	m
							蓋版	
							227	枚
							蓋版	
							57	枚
							蓋版	
							4	枚

07-実施--一般-0003-当初

＊ ＊ 本工事費 ＊ ＊ 内訳表

頁0-0003

費目・工種・施工名称・管理費区分	数	量	単	位	金	額	備	考
							プレキャスト集水桝	
							5	基
							取付管布設および支管取付工	
							5	箇所
構造物撤去工								
				式		384,228		
							舗装版切断	
							20	m
							舗装版破碎	
							560	m2
							構造物とりこわし	
							4	m3
							殻運搬	
							28	m3
							殻運搬	
							4	m3
							廃材処理費	
							アスファルト舗装廃材	
							65	t

07-実施--一般-0003-当初

＊ ＊ 本工事費 ＊ ＊ 内訳表

頁0-0004

費目・工種・施工名称・管理費区分		数	量	単	位	金	額	備	考
								廃材処理費 コンクリート殻廃材(無筋)	
舗装								10	t
舗装工								式	7, 107, 326
								式	5, 985, 264
								下層路盤(車道・路肩部)	
								1, 580	m2
								上層路盤(車道・路肩部)	
								1, 550	m2
								表層(車道・路肩部)	
縁石工								1, 550	m2
								式	773, 900
								地先境界ﾌﾞﾛｯｸ	
防護柵工								142	m
								式	194, 668

07-実施--一般-0003-当初

＊ ＊ 本工事費 ＊ ＊ 内訳表

頁0-0005

費目・工種・施工名称・管理費区分		数	量	単	位	金	額	備	考
								防護柵(横断・転落防止柵)設置工	
								4	m
区画線工									
					式		153,494		
								区画線設置	
								220	m
								区画線設置	
								3	m
								区画線設置	
								15	m
								区画線設置	
								60	m
仮設工									
					式		1,046,500		
仮設工									
					式		1,046,500		
								交通誘導警備員B	
								57.5	人日

07-実施--一般-0003-当初

＊ ＊ 本工事費 ＊ ＊ 内訳表

頁0-0006

費目・工種・施工名称・管理費区分		数	量	単	位	金	額	備	考
直接工事費									
							16,329,910		
共通仮設費（率分）									
							2,343,000		
共通仮設費計									
							2,343,000		
純工事費									
							18,672,910		
現場管理費（率分）									
							6,991,000		
現場管理費計									
							6,991,000		
工事原価									
							25,663,910		
工事原価計									
							25,663,910		
一般管理費等									
							5,136,090		

07-実施-一般-0003-当初

＊ ＊ 本工事費 ＊ ＊ 内訳表

頁0-0007

費目・工種・施工名称・管理費区分		数	量	単	位	金	額	備	考
契約保証費									
							10,000		
一般管理費等計									
							5,146,090		
工事価格									
							30,810,000		

07-実施--一般-0003-当初